

Addendum Number M1

Museum Center Expansion
Dickinson, North Dakota

GT Architecture
401 West Villard Street Suite 206
Dickinson, ND 58601

Feb. 24, 2026

THE FOLLOWING ADDENDUM ITEMS SHALL BECOME A PART OF THE PLANS AND SPECIFICATIONS FOR THE ABOVE REFERENCED PROJECT AND ITS RECEIPT SHALL BE ACKNOWLEDGED ON THE BID FORM.

THE FOLLOWING ITEMS REFER TO THE SPECIFICATIONS:

Item No. 1: None in this addendum

THE FOLLOWING ITEMS REFER TO THE DRAWINGS:

Item No. 2: Sheet M402

Clarification of keynote 49 (replace keynote 49 with the following).
“SOURCE CAPTURE ARMS EXTERNAL SUPPORT STRUCTURE SERIES 15000-EXT (16’). ARM TO PIVOT 180 DEGREES AT THE WALL PLUS BE FULLY ADJUSTABLE IN 2 OTHER LOCATIONS ON THE BOOM ARM AND CONTAIN A MINIMUM OF 3 BENDABLE ELBOWS IN THE EXTERIOR SUPPORT BRACE. AT A MOUNTING HEIGHT OF 8 FEET 3” INCHES, REACHING A WORKING HEIGHT OF 30 INCHES, PROVIDE ENOUGH FLEX HOSE TO COVER A 15 FOOT RADIUS AS SHOWN ON THE DRAWINGS. TERMINATE WITH THE APPROVED NOZZLE THAT COMES WITH THE BOOM ARM SYSTEM BY MONOXIVENT. DUCT SIZE PER ARM TO BE 6” AS SHOWN ON THE DRAWINGS. PROVIDE DUCT AND FLEX HOSE CAPABLE OF 5000 FPM.”

Item No. 3: Sheet M402

Clarification of 12x8 exhaust duct
Add a counter weighted back draft damper to the 12x8 exhaust duct.
Place damper as close as possible to the new exterior louver. See plan 2/M402 lower right corner of the plan.

PRIOR APPROVALS

THE FOLLOWING ITEMS ARE APPROVED FOR BIDDING CONTINGENT UPON MEETING THE SPECIFICATIONS:

SECTION

APPROVED

23 70 00

Rooftop Units by CaptiveAire

END OF ADDENDUM