

## Addendum Number M2

Museum Center Expansion  
Dickinson, North Dakota

GT Architecture  
401 West Villard Street Suite 206  
Dickinson, ND 58601

March 2, 2026

**THE FOLLOWING ADDENDUM ITEMS SHALL BECOME A PART OF THE PLANS AND SPECIFICATIONS FOR THE ABOVE REFERENCED PROJECT AND ITS RECEIPT SHALL BE ACKNOWLEDGED ON THE BID FORM.**

---

### THE FOLLOWING ITEMS REFER TO THE SPECIFICATIONS:

Item No. 1: None in this addendum

### THE FOLLOWING ITEMS REFER TO THE DRAWINGS:

Item No. 2: Sheet M102

Clarification of keynote D27 (add the following to keynote 27).

“REMOVE COMPLETE THE HUMIDIFIER. REMOVE COLD WATER LINE COMPLETE AND CAP AT THE MAIN. PATCH DUCTWORK AS REQUIRED. VERIFY DUCT SIZE. MATCH EXISTING.”

This includes the (3) three furnaces that are getting new condensing units and new cooling coils.

Item No. 3: Sheet M101

Refer to keynote D39 sump pump removal. This sump is located on the opposite side of the wall in the collections room.

Apply keynote D39 to the sump pump in the 3D printing room / storage. Remove all exposed vent piping and discharge piping out the North wall. Cap all abandoned piping.

Item No. 4: Sheet M402

Air compressor clarification: This contractor provides and installs the air compressor as scheduled on the drawings.

Provide vibration isolation for the air compressor. Options listed below:

1. Neoprene rubber pads specifically designed for large equipment vibration isolation.

Item No. 5: Sheet M602

Refer to keynote D39 sump pump removal. This sump is located on the opposite side of the wall in the collections room.

Apply keynote D39 to the sump pump in the 3D printing room / storage. Remove all exposed vent piping and discharge piping out the North wall. Cap all abandoned piping.

Item No. 6: Sheet M701

Refer to the water heater schedule. Manufacturer column: Replace "Rheem" with "AO Smith".

Item No. 7: Sheet M601

Refer to keynote detail 12/M601:

1. Domestic water expansion tank to be equivalent to Amtrol ST-5, diaphragm, rated for domestic water, 2 gallon tank volume.
2. Domestic water recirculating pump equivalent to Grundfos MAGNA3 32-60F

## **PRIOR APPROVALS**

**THE FOLLOWING ITEMS ARE APPROVED FOR BIDDING CONTINGENT UPON MEETING THE SPECIFICATIONS:**

### **SECTION**

### **APPROVED**

22 30 00

Water Heater by PVI (Conquest)

23 34 00

Dust Collector by Camfil – dust collector must meet all specifications, 15 hp motor capable of 9" of static pressure. Contractor is responsible for any duct configuration changes that may occur.

END OF ADDENDUM